

ROUGH INITIAL BUDGET WORKSHEET

Farber-Haines Residence

Landscape Construction Work Outline ^{1.0}

Site Plan dated 03.17.26



MARPA

<u>DESCRIPTION</u>	<u>QTY</u>	<u>UNIT</u>	<u>UNIT PRICE</u>	<u>PRICE</u>
SITE PREP ^{2.0}				\$8,500.00
Crew / Trailer / Machinery Mobilization	1	ea	\$1,500.00	\$1,500.00
Debris Hauling & Disposal	1	ea	\$2,000.00	\$2,000.00
Final Site Property Cleanup, Detailing - ALLOWANCE ^{10.0}	1	ea	\$5,000.00	\$5,000.00
DRAINAGE ALLOWANCE ^{10.0} (PENDING CIVIL DESIGN)				\$20,300.00
12" Area Drain / Elbow / Fittings @ Downspouts	9	ea	\$500.00	\$4,500.00
Downspout Extension w/ Popup Fitting	135	lf	\$80.00	\$10,800.00
Site Drainage ALLOWANCE ^{10.0}	1	ea	\$5,000.00	\$5,000.00
WALLS - ALLOWANCE ^{10.0}				\$55,368.00
Concrete Wall (0'-8"W x 2'-0"H) w/ Spread Footer	52	lf	\$374.00	\$19,448.00
Concrete Pump	4	ea	\$605.00	\$2,420.00
Driveway Wall - Steel (~3'-0" H max.)	45	lf	\$300.00	\$13,500.00
Concrete Landscape Block Wall w/ French Drain w/ Cap (4'-0" H)	160	ff	\$125.00	\$20,000.00
Cost Savings Options ^{12.0}				
Remove Driveway Wall	1	ea	-\$13,500.00	-\$13,500.00
GRADING - ALLOWANCE ^{10.0}				\$8,500.00
Fine Grading - ALLOWANCE ^{10.0}	1	ea	\$8,500.00	\$8,500.00
BOULDERS ^{3.0}				\$20,560.00
Boulders - Granite, Avg 1.5 ton 18"x18"x36"	30	ton	\$650.00	\$19,500.00
Delivery - Boulders	2	ea	\$530.00	\$1,060.00
POOL - ALLOWANCE ^{9.0 + 10.0}				\$354,400.00
Pool (10'-0" x 25'-0" Custom Shotcrete Shell w/ Equipment)	1	ea	\$225,000.00	\$225,000.00
Permit	1	ea	\$9,000.00	\$9,000.00
<u>Preparation + Finish:</u>				
Surveying and Staking	1	ea	\$500.00	\$500.00
Excavation and Backfill	1	ea	\$25,000.00	\$25,000.00
Trenching for Pool Plumbing (2' Depth)	80	lf	\$35.00	\$2,800.00
Core Drill + LinkSeal to Mech Room	1	ea	\$4,500.00	\$4,500.00
Perimeter Drain Pool	80	lf	\$70.00	\$5,600.00
Bonding of Patio	1	ea	\$1,800.00	\$1,800.00
Auto Cover Brackets - Design and Material TBD	1	ea	\$12,000.00	\$12,000.00
<u>Utilities:</u>				
Energy Offsets Engineering Consultant, TBD	1	ea	\$3,000.00	\$3,000.00
Electrical Wiring to Equipment In Mech Room	1	ea	\$15,600.00	\$15,600.00

ROUGH INITIAL BUDGET WORKSHEET

Plumbing and Autofill Hookups to Equipment	1	ea	\$3,600.00	\$3,600.00
Internet Hookup to Equipment	1	ea	\$1,000.00	\$1,000.00
<u>Excluded, By Others:</u>				
Mech Room Modifications, Concrete Floor Curb				
Utility Supply (Electric, Water and Internet), Hose Bib @ Mech Roc				
Drainage - Recommended Two Floor Drains in Mech Room to Daylight				
Fresh Air Intake and Exhaust In Mech Room				
<u>Spa - Standalone w/ Surround</u>				
Spa - ALLOWANCE ^{10.0}	1	ea	\$45,000.00	\$45,000.00
Cost Savings Options ^{12.0}				
Replace w/ Fiberglass Pool Shell	1	ea	-\$87,000.00	-\$87,000.00

FLATWORK / PAVING ^{4.0} \$88,361.85

<u>Preparation + Finish</u>				
Sleeving - ALLOWANCE ^{10.0}	100	lf	\$30.00	\$3,000.00
<u>Concrete Patios</u>				
Road Base 3", install compacted	40	ton	\$110.00	\$4,400.00
Concrete 3 1/2", Sand-Finish	2,200	sf	\$22.55	\$49,610.00
Added Color	2,200	sf	\$2.00	\$4,400.00
Stairs	80	lf	\$55.00	\$4,400.00
Stair Light Housing	10	ea	\$55.00	\$550.00
Concrete Pump	2	ea	\$605.00	\$1,210.00
Expansion Joint and Sealant - ALLOWANCE ^{10.0}	195	lf	\$25.00	\$4,875.00
<u>Coping at Pool</u>				
Concrete 3 5/16", Sand-Finish	47	sf	\$39.05	\$1,835.35
Added Color	47	sf	\$2.00	\$94.00
Concrete Pump	1	ea	\$605.00	\$605.00
<u>Steppers at Backyard</u>				
	15	sf	\$80.00	\$1,200.00
<u>Concrete Stairs @ Basement, by Others</u>				
Rigid Foam Insulation for Snowmelt	2,215	sf	\$5.50	\$12,182.50

IRRIGATION ALLOWANCE ^{6.0 + 10.0} \$39,475.00

Ditch Integration ALLOWANCE ^{10.0}	1	ea	\$15,000.00	\$15,000.00
4" Pop Up (Low Groundcover Areas / Lawn)	10	ea	\$1,375.00	\$13,750.00
Drip (Plants)	4	ea	\$1,950.00	\$7,800.00
Controller - Hunter HYDRAWISE Exterior Mounted	1	ea	\$1,500.00	\$1,500.00
Valve Box - Amatek Jumbo with Green Lid / Fittings	3	ea	\$475.00	\$1,425.00

GROUNDCOVERS ^{5.0} \$138,138.15

Edging - Bar Stock Steel @ Special Planters	100	lf	\$38.00	\$3,800.00
Edging - Roll Top @ Lawn, Gravel & Bed Edges	1,015	lf	\$17.25	\$17,508.75
Amended Top Soil - 6" Depth @ Beds	75	yd	\$341.00	\$25,575.00
Amended Top Soil - 24" Depth @ Berms	50	yd	\$341.00	\$17,050.00
Soil Prep @ Beds - Compost (4YD/1000 SF)	7,000	sf	\$1.07	\$7,476.00
Soil Prep @ Berms - Compost (4YD/1000 SF)	500	sf	\$1.07	\$534.00
Mulch - Wood Depth (no fabric)	7,500	sf	\$2.05	\$15,375.00

ROUGH INITIAL BUDGET WORKSHEET

Delivery - Mulch	3	ea	\$415.80	\$1,247.40
Sod - Kentucky Bluegrass w/o Soil Prep	4,000	sf	\$4.50	\$18,000.00
Soil Prep @ Sod - Lawn Compost (4 YD/1000 SF)	4,000	sf	\$1.07	\$4,272.00
Paths - 25% 3/8" Granite Chip + 75% Breeze, 3" Depth w/ Fabric	1,400	sf	\$9.25	\$12,950.00
Gravel - Granite 3/8" @ 3" Depth (w/ fabric)	3,000	sf	\$3.90	\$11,700.00
Delivery - General	10	ea	\$265.00	\$2,650.00

Cost Savings Options ^{12.0}

Remove Back Yard Berm (Replace with Sod)

Amended Top Soil - 24" Depth @ Berms	-27	cy	\$341.00	-\$9,093.33
Soil Prep - Compost (4 YD/1000 SF) @ Berms	-360	sf	\$1.07	-\$384.48
Mulch - Wood" Depth (no fabric)	-360	sf	\$3.25	-\$1,170.00
Sod - Kentucky Bluegrass w/o Soil Prep	360	sf	\$4.50	\$1,620.00
Soil Prep @ Sod - Lawn Compost (4 YD/1000 SF)	360	sf	\$1.07	\$384.48
Eliminate Edging at Pathway	-415	lf	\$17.25	-\$7,158.75
Eliminate Special Edging at Planters	-100	lf	\$38.00	-\$3,800.00

PLANT MATERIAL - ALLOWANCE ^{8.0 + 10.0}

\$118,753.18

Groundcover - Perennial Flat (F32)	40	ea	\$327.39	\$13,095.60
Grass (#1)	150	ea	\$51.85	\$7,777.50
Perennial (#1)	150	ea	\$48.64	\$7,296.00
Shrub - Deciduous (#5)	45	ea	\$186.04	\$8,371.80
Shrub - Evergreen (#6)	15	ea	\$378.52	\$5,677.74
Trees - Deciduous (2" Caliper, 6-8' H)	26	ea	\$930.00	\$24,180.00
Trees - Deciduous (2+" Caliper, 8-10' H)	12	ea	\$1,358.27	\$16,299.24
Trees - Evergreen (6-8' H)	15	ea	\$1,649.52	\$24,742.80
Delivery - Plants	5	ea	\$302.50	\$1,512.50
Character Pine by Marpa (6' H)	2	ea	\$4,000.00	\$8,000.00
Character Pine Install + Delivery	2	ea	\$900.00	\$1,800.00

Cost Savings Options ^{12.0}

Remove Back Yard Berm

Groundcover Flat (F32)	-4	ea	\$327.39	-\$1,186.79
Grass (#1)	-40	ea	\$59.85	-\$2,394.00
Perennial (#1)	-40	ea	\$48.64	-\$1,945.60
Shrub - Evergreen (#6)	-3	ea	\$378.52	-\$1,135.55

DRIVEWAY - ALLOWANCE ^{10.0}

\$60,200.50

Broom-Finish Concrete Slab 5" w/ Sawcut Joints	2,135	sf	\$19.80	\$42,273.00
Prep 4" Road Base, Stabilizer, Geotextile, (Excludes Demo + Debris)	35	ton	\$110.00	\$3,850.00
Expansion Joint and Sealant - ALLOWANCE ^{10.0}	45	lf	\$25.00	\$1,125.00
Concrete Pump	2	ea	\$605.00	\$1,210.00
Rigid Foam Insulation for Snowmelt	2,135	sf	\$5.50	\$11,742.50

FENCING - ALLOWANCE ^{10.0}

\$28,268.25

Fence Removal	300	lf	\$5.00	\$1,500.00
Wood (6'-0"H) - Screening @ Property Lines	335	lf	\$63.80	\$21,373.00
Gate	5	ea	\$600.00	\$3,000.00

ROUGH INITIAL BUDGET WORKSHEET

Staining	335	lf	\$7.15	\$2,395.25
Cost Savings Options ^{12.0}				
Remove Front Yard @ Setback	1	ea	-\$10,254.75	-\$10,254.75

LIGHTING - ALLOWANCE ^{7.0 + 10.0} \$27,284.00

Accent Light (Fixture, Install, Wire)	20	ea	\$414.00	\$8,280.00
Path Light (Fixture, Install, Wire)	12	ea	\$453.00	\$5,436.00
Ground Light (Fixture, Install, Wire)	16	ea	\$453.00	\$7,248.00
Wall Light (Fixture, Install, Wire)	8	ea	\$550.00	\$4,400.00
Transformer - FX Luxor - 300 W / Wire / Programming	1	ea	\$1,920.00	\$1,920.00
Cost Savings Options ^{12.0}				
Reduce 33%	1	ea	-\$9,003.72	-\$9,003.72

RAISED PLANTERS ALLOWANCE ^{10.0} \$29,350.00

Steel - Large Sizes 12' L x 4 to 8' W x 2' H	3	ea	\$7,000.00	\$21,000.00
Delivery - Steel	1	ea	\$2,500.00	\$2,500.00
Wood - Garden Beds 3' W x 5' L	3	ea	\$1,200.00	\$3,600.00
Delivery - General	3	ea	\$750.00	\$2,250.00
Cost Savings Options ^{12.0}				
Eliminate Garden Beds	-6	ea	\$1,200.00	-\$7,200.00

GENERAL ALLOWANCES ^{10.0} \$25,500.00

Trenching / Utilities / Undergrounds	1	ea	\$10,000.00	\$10,000.00
Steel - Curved Wall	1	ea	\$10,000.00	\$10,000.00
Trash Enclosure	1	ea	\$5,500.00	\$5,500.00
Cost Savings Options ^{12.0}				
Eliminate Steel Wall	-1	ea	\$10,000.00	-\$10,000.00

FURNISHINGS - SHADE PARASOL ALLOWANCE ^{10.0} \$24,055.24

Shade Parasol (Touch 10' x 20' OM Max Dual Cantilever) + Install	1	ea	\$16,112.76	\$16,112.76
Shade Parasol Cover	1	ea	\$902.48	\$902.48
Shade Parasol Anchor Base	1	ea	\$5,840.00	\$5,840.00
Shipping + Tax	1	ea	\$1,200.00	\$1,200.00

Subtotal \$ 1,047,014.17
Marpa Contracting & Project Management Fee \$ 209,402.83
Project Foreman Fee \$ 15,705.21
Project Liability Insurance (0.85%) \$ 8,899.62

TOTAL \$ 1,281,021.84

TOTAL W/ COST SAVINGS OPTIONS \$ 1,081,319.12

Rough Budget Contingency (Not Included in Total, Shown for Reference Only) ^{11.0} \$ 104,701.42

ROUGH INITIAL BUDGET WORKSHEET

ADD OPTIONS 12.0

AUTO GATE - ALLOWANCE 10.0 **\$56,500.00**

Auto Gate + Equipment @ Driveway	1	ea	\$38,000.00	\$38,000.00
Excavation + Backfill	1	ea	\$2,300.00	\$2,300.00
Concrete Footers 4'x4'x4' (Two Pours)	1	ea	\$5,200.00	\$5,200.00
Trenching / Conduit	100	lf	\$35.00	\$3,500.00
Electrical + Internet Work	1	ea	\$7,500.00	\$7,500.00
AV and Integration to Smart Home System, By Other				

FENCING AT FRONT YARD **\$10,254.75**

Wood (3'-0"H) - Privacy @ Front Yard	165	lf	\$55.00	\$9,075.00
Staining	165	lf	\$7.15	\$1,179.75

FIRE PIT ALLOWANCE 10.0 **\$15,500.00**

Wood Burning Pit - Steel	1	ea	\$9,000.00	\$9,000.00
Wood Storage Rack	1	ea	\$6,500.00	\$6,500.00

OUTDOOR KITCHEN ALLOWANCE 10.0 **\$24,000.00**

Varies Per Design	1	ea	\$24,000.00	\$24,000.00
-------------------	---	----	-------------	-------------

SPA **\$156,900.00**

Spa w/ Autocover & Equipment	1	ea	\$110,000.00	\$110,000.00
Permit	1	ea	\$4,400.00	\$4,400.00
Surveying and Staking	1	ea	\$500.00	\$500.00
Excavation and Backfill	1	ea	\$15,000.00	\$15,000.00
Coping at Spa	1	ea	\$2,000.00	\$2,000.00
Electrical Wiring	1	ea	\$12,000.00	\$12,000.00
Water Supply & Hookup	1	ea	\$2,500.00	\$2,500.00
Internet Supply & Hookup	1	ea	\$1,500.00	\$1,500.00
Auto Cover Brackets - Design and Material TBD	1	ea	\$9,000.00	\$9,000.00

TRENCH DRAIN (Pending Civil) **\$8,375.00**

Trench Drain @ Driveway - ALLOWANCE 10.0	40	lf	\$125.00	\$5,000.00
Trench Drain @ Pool - ALLOWANCE 10.0	27	lf	\$125.00	\$3,375.00

WALLS - STONE FASCIA **\$25,245.00**

Stone Cladding, Materials + Install (Pending Material)	327	ff	\$60.00	\$19,620.00
Stone Cap, Materials + Install (Pending Material)	75	sf	\$75.00	\$5,625.00

Subtotal	\$	296,774.75
Marpa Contracting & Project Management Fee	\$	59,354.95
Project Foreman Fee	\$	4,451.62
Project Liability Insurance (0.85%)	\$	2,522.59
TOTAL	\$	363,103.91

Schematic Design Budget 1

Notes

Farber-Haines Residence

Budget Notes

Site Plan dated 03.17.26



EXCLUSIONS

Budget does not include: Furniture, Rough Grading, Landscape Maintenance, Subgrade Drainage, Snowmelt Equipment and Install, Third Party Inspections, Tree Removal, or anything not explicitly stated above.

NOTES

1.0 This budget has been prepared based off of the plans dated in the title. Assumes site will be delivered in a clean and orderly manner. Due to inflation and tariffs, pricing is subject to change throughout the course of construction and will be billed at actual price incurred for completed work. Due to the increased demand for imported goods as well as global supply chain issues, any ordered products and materials are subject to long lead times that may change over the course of the project, therefore any delivery date provided on orders are to be viewed as an approximate target date and cannot be guaranteed. Does not include Landscape Maintenance. **Pricing is based off yearly averages as observed by Marpa Landscape Architecture and may vary compared to firm bids. The plans referenced are at a Schematic Design level, therefore there is the possibility for unknown details, as well as additional unknown / unidentified costs. This document is not a firm bid and is not to be used for contracts or construction. Marpa Recommends a 10% contingency is planned upon by the homeowner for unforeseen events which occur during the installation process.**

2.0 Assumes use of driveway for access. Assumes job trailer can be parked on site. Does not include street occupancy or parking permits if needed. Marpa is not liable for regular wear and tear to public right of way (roads, alleys, sidewalks, etc.) that are necessary to use for access to the project. Transplanting existing trees is a risky process, with typically 50% success rate. Transplanted trees are not covered under warranty. Does not include permit or tax reconciliation fees that may be required by the relevant government authority after the completion of the Project.

3.0 Actual boulder size and locations will vary from plan, based on selection available at quarry / landscape yard. Trips to select boulders are subject to mileage reimbursement at the current IRS Standard Mileage Rate.

4.0 Sand-Finish concrete requires at least 3-4 continuous nights of temperatures above 45° to pour and cure. Control joints to be cut into concrete per the plans to help control the areas in which concrete is likely to crack, not prevent cracking. Hairline cracks may appear outside of the control joints. The presence of a hairline crack does not mean the installation was done improperly, nor does it indicate a flaw in the concrete or structural issues. The use of snow melt products on finished concrete will cause corrosion within the layers of concrete, resulting in pitting and cracking; any damage resulting from the use of snow melt products is not covered by warranty.

5.0 Sod requires minimum 2 weeks to set with no traffic of any kind. All warranties on sod, which is planted between September and April, will be considered waived, voided, and null unless the Client agrees to have the Contractor perform winter watering services as needed during the winter months while irrigation systems are winterized.

6.0 Irrigation pricing assumes points of connection, electrical and WiFi will be provided by other. Assumes controllers are to be wall mounted in the same location as the points of connection, unless otherwise noted. Final design and pressure at POCs at time of installation may affect final price. Does not include irrigation winterization and / or start up during the season following installation.

7.0 Assumes outlets to be provided at house for lighting transformer. Integration of lighting into house to be under the House Contractor's scope. Homeowner to assume responsibility should lighting plan not be dark sky compliant.

8.0 Plant species, quantities, and size are subject to change based on availability at time of planting, as well as creative direction from Landscape Architect. Trips to select plant material are subject to mileage reimbursement at the current IRS Standard Mileage Rate. Planting window for grasses, perennials, and shrubs is after last frost in the spring and before first frost in the fall. All warranties on plant material will be considered waived, voided, and null unless the Client agrees to have the Contractor perform winter watering services as needed during the winter months while irrigation systems are winterized.

9.0 Additional cost may be required for: tenting and / or heating at time of plaster (pending cold weather temperatures), dewatering and perimeter drain (if ground water is encountered during excavation).

10.0 Allowances are rough estimates for cost of work. Actual prices will be furnished at time of invoicing.

11.0 Rough Budget Contingency is included to cover unforeseen details and costs, as the plans are not at a Construction Document level. This cost is a percentage calculation and meant to convey that, though thorough, this document may be missing costs in certain areas.

12.0 Add Options are not included in the Project Total or scope of work. Should they be added to the scope, they will be presented as a Change Order and include a Marpa Design & Planning, Oversight, Quality Control & Contracting Fee.